

INVITATION FOR BIDS ON OCONTO COUNTY FOREST

Sealed bids will be received by the Forest and Parks Administrator, on behalf of the Land and Water Resources Committee at Oconto County Courthouse, 301 Washington Street, Oconto, WI up to **1:00 p.m. on Monday, June 3, 2024**. There is a potential there could be a quorum of the **Land and Water Resources Committee**. Timber sale maps, prospectus, bid forms, and detailed information on each timber tract can be obtained by contacting the Forest & Parks Department at 920-834-6995 or fpr@co.oconto.wi.us. Documents may also be found online at <http://www.co.oconto.wi.us/> under the NEWS heading.

There are **4 timber tracts** for sale totaling **179 acres** and containing an estimated volume of **213.5 MBF** and **8,130 Tons** on a variety of species. Timber produced on Oconto County forest is dual third party certified.

Oconto County reserves the right to reject any and all bids. **Bids will be open on Monday, June 3, 2024 at 1:00pm.**

Land and Water Resources Committee

Timber Sale Prospectus

PROPERTY: Oconto County Forest

TRACT: 13-21

LOCATION: NWNW, NENW, Sec 14; NENW, NWNW, SENW, NWNE, NENE, NESW, NWSW, SESW, NWSE Sec 15; NWNW, NENW, Sec 22 T29N R22E

TOWN NAME: Little River

SALE AREA: 99 Acres

Bid Opening: Time: May 6th, 2024 at 1:00pm at Oconto County Courthouse. Any and all bids may be rejected.

Species	Product	Volume (Tons)	Weight Conversion (Tons per Cord)
Mixed Hardwood ¹	Pulp/Bolts	2500 Tons	2.400
Aspen	All	1400 Tons	2.250
Oak	Pulp/Bolts	130 Tons	2.750
Red Maple	Logs	60 MBF	
Ash	Logs	55 MBF	
Oak ²	Logs	15 MBF	
Mixed Hardwood ³	Logs	4 MBF	

¹ Mixed hardwood pulp includes all hardwood species. Mixed hardwood pulp is comprised of an estimated 62% ash, 30% red maple, 6% cherry, 2% birch. It also includes a small amount of elm and beech.

² Oak logs are estimated at 80% northern red oak and 20% northern pin (scrub) oak.

³ Mixed hardwood logs are estimated at 50% cherry, 45% birch, with the rest being elm and beech.

SALE BOUNDARY: Red paint lines indicate cutting boundaries. Blue paint lines indicate cutting boundaries with private ownerships. If a discrepancy exists between this written description and the map, then this written description will prevail.

CUTTING SPECS:

Coppice Harvest 90 acres: Cut all trees >1" diameter except conifers and green marked trees. Leave all dead standing trees.

Salvage Harvest 9 acres: Cut all trees >5" diameter except conifers, good quality white oak, and green painted trees.

SPECIAL SALE CONSIDERATIONS:

- Well frozen ground conditions required.
- Do not leave tops in non-forested wetlands. Lop slash to 33" in height. No slash within 15' of County Line Road.
- Do not drop trees across or leave slash across blue paint lines.
- Possible access through private land to access southern cutting units.
- Mats maybe needed to cross 2 small drainages as indicated on map.
- Equipment must be clean and free of debris when arriving on-site. This includes mats.
- No operating equipment in patches of phragmites as indicated on map.

UTILIZATION STANDARDS: Cord wood (aka pulp) must be utilized to a 4-inch top diameter for hardwoods and 4-inch for softwood. Logs will be defined as 8 feet or longer to an 11-inch small end diameter for hardwoods and 9-inch small end diameter for soft woods.

SCALING METHOD: Review contract regarding specific scaling procedures & specifications. Ensure all employees, sub-contractors, etc. understand scaling & hauling procedures & the species/products specific to the sale.

A list of anticipated wood vendors is required prior to hauling. Cord wood delivered to approved mills with certified scales must use truck/mill ticket system. Cord wood not going to mill with certified scale will be scaled on the landing. Sawtimber delivered to approved mills (3rd party log scale) may be hauled using the ticket system. Sawtimber not going to approved mills (not 3rd party scaled) must be scaled on the landing. Oconto County reserves the right to scale any & all wood products. Piles must be sorted according to species listed per contract. All stumpage payments are due upon receipt of the billing invoice. If payment is not received by close of business, 30 days from the date of the invoice, a penalty of 1.5% of the value on the invoice will be added each month. In addition, purchaser will be required to pay for forest products prior to removal until all invoices are paid in full.

CERTIFICATION: Logging Contractor (not necessarily the purchaser if subcontracted) must document compliance with Wisconsin SFI training standard. Successful bidders when signing a contract shall provide the county with workmen's compensation as required by Wisconsin Law and liability insurance with minimum combined single limit of \$1,000,000. Sub-contractors are also required to provide workmen's compensation and liability insurance as required by Wisconsin Law.









BOND REQUIREMENTS: A 10% Bid Bond must accompany each bid. Bond can be in the form of personal check, certified check, bank draft, or money order. Oconto County may retain the bid bond if the successful bidder fails to sign the contract. The Purchaser within 6 weeks of bid opening and before work is commenced must submit a 20% Performance Bond acceptable to the County.

CONTRACT: A 48-month contract ending TBD will apply to this tract. A sample of the timber sale contract, which may contain additional provisions, is available upon request. Timber sale contracts may not be assigned.

SEE MAP on PAGE 2

Tract 13-21 County Line Aspen Sale

LEGEND

-  Gate
-  Phragmites - Avoid
-  Stream
-  Trails
-  County Line Road
-  Oconto County Forest
-  Coppice Harvest: Cut all trees >1" diameter except conifers and green painted trees. Leave all dead standing trees. 90 acres.
-  Salvage Harvest: Cut all trees >5" diameter except conifers, good quality white oak, and green marked trees. 9 acres.


Well Frozen Ground Harvesting Only.

Contract # _____

Contractor _____



99 Acres



Species	Product	Volume
Mixed Hardwood	Pulp/Bolts	2500 Tons
Aspen	All	1400 Tons
Oak	Pulp/Bolts	130 Tons
Red Maple	Logs	60 MBF
Ash	Logs	55 MBF
Oak	Logs	15 MBF
Mixed Hardwood	Logs	4 MBF

SPECIAL SALE CONSIDERATIONS:

- Well frozen ground conditions required.
- Do not leave tops in non-forested wetlands. Lop slash to 33" in height.
- Do not drop trees or leave slash across blue paint line.
- Possible access through private land to access southern cutting units.
- Mats maybe needed to cross 2 small drainages as indicated on map.
- Equipment must be clean and free of debris when arriving on-site.
- No operating equipment in patches of phragmites as indicated on map.
- This map is not a survey of actual boundary lines.

NWNW, NENW, Sec 14; NENW, NWNW, SENW,
 NWNE, NENE, NESW, NWSW, SESW, NWSE
 Sec 15; NWNW, NENW, Sec 22 T29N R22E
 Town of Little River Scale 4" = 1 mile

Kaufman

Timber Sale Prospectus

PROPERTY: Oconto County Forest

TRACT: 01-24

LOCATION: SESE Sec 9, SWSW Sec 10, SESW Sec 15 27N R20E

TOWN NAME: Abrams

SALE AREA: 30 Acres

Bid Opening: Time: May 6th, 2024, at 1:00pm at Oconto County Courthouse. Any and all bids may be rejected.

Species	Product	Volume (Tons)	Weight Conversion (Tons per Cord)
Mixed Hardwood ¹	Pulp/Bolts	1600 Tons	2.400
Basswood	Pulp/Bolts	65 Tons	1.925
Oak	Pulp/Bolts	35 Tons	2.750
Aspen	All	25 Tons	2.250
Balsam Fir ²	All	25 Tons	2.125
Red Maple ³	Logs	60 MBF	
Mixed Hardwood ⁴	Logs	15 MBF	
Red Oak ⁵	Logs	2 MBF	

¹ Mixed hardwood pulp/bolts are approx. 80% red maple, 11% ash, 5% sugar maple, 4% other

² Balsam fir is mostly balsam fir but includes all conifers.

³ Red maple logs include an estimated 2% sugar maple.

⁴ Mixed hardwood logs are an estimated 56% ash, 39% basswood & 5% other hardwoods.

⁵ Red oak logs are northern red oak and may contain a small amount of white oak.

SALE BOUNDARY: Red & Blue paint lines indicate cutting boundaries. If a discrepancy exists between this written description and the map, then this written description will prevail.

CUTTING SPECS: Overstory Removal Harvest (24 acres): Cut all trees >1" diameter except hemlock, cedar & trees marked in green paint. Sever all oak saplings damaged in harvest operations. Can reach across red paint lines to cut ash with processor but no crossing red paint line with equipment. Leave all dead standing trees. Frozen or very dry soil requirements No harvesting April 15th - July 15th.

Thinning (6 acres): Cut all aspen, ash & trees marked in orange paint. Can reach across red paint lines to cut ash with processor but no crossing red paint line with equipment. Leave all dead standing trees. No harvesting April 15th - July 15th.

Special Sale considerations all units

-Slash height shall not exceed 33". Do not leave any slash in any non-forested wetlands.

-Equipment must be clean and free of debris when arriving on-site.

-Do not cross red or blue paint lines. Do not leave tops across blue paint lines.

-Leave all existing trails in good condition for the duration of the harvest operations & clear of debris.

-Replace all berms upon sale completion.

-All decking areas must be pre-approved by Oconto County Forestry & Parks staff.

-If harvesting without frozen ground conditions, a DNR stream crossing permit may be needed to access sale areas. With a minimum of 2 months advanced notice from purchaser, WDNR or Oconto County Forestry staff will apply for stream crossing permit.

-Southern cutting units must be accessed through private lands. Purchaser is responsible for acquiring permission to access through private lands. Contact DNR Forester Steve Kaufman 920-360-1290 for landowner contact information and possible access points.

UTILIZATION STANDARDS: Cord wood (aka pulp) must be utilized to a 4-inch top diameter for hardwoods and 4-inch for softwood. Logs will be defined as 8 feet or longer to an 11-inch small end diameter for hardwoods and 9-inch small end diameter for soft woods.

SCALING METHOD: Review contract regarding specific scaling procedures & specifications. Ensure all employees, sub-contractors, etc. understand scaling & hauling procedures & the species/products specific to the sale.







A list of anticipated wood vendors is required prior to hauling. Cord wood delivered to approved mills with certified scales must use truck/mill ticket system. Cord wood not going to mill with certified scale will be scaled on the landing. Sawtimber delivered to approved mills (3rd party log scale) may be hauled using the ticket system. Sawtimber not going to approved mills (not 3rd party scaled) must be scaled on the landing. Oconto County reserves the right to scale any & all wood products. Piles must be sorted according to species listed per contract. All stumpage payments are due upon receipt of the billing invoice. If payment is not received by close of business, 30 days from the date of the invoice, a penalty of 1.5% of the value on the invoice will be added each month. In addition, purchaser will be required to pay for forest products prior to removal until all invoices are paid in full.


CERTIFICATION: Logging Contractor (not necessarily the purchaser if subcontracted) must document compliance with Wisconsin SFI training standard. Successful bidders when signing a contract shall provide the county with workmen's compensation as required by Wisconsin Law and liability insurance with minimum combined single limit of \$1,000,000. Sub-contractors are also required to provide workmen's compensation and liability insurance as required by Wisconsin Law.


BOND REQUIREMENTS: A 10% Bid Bond must accompany each bid. Bond can be in the form of personal check, certified check, bank draft, or money order. Oconto County may retain the bid bond if the successful bidder fails to sign the contract. The Purchaser within 6 weeks of bid opening and before work is commenced must submit a 20% Performance Bond acceptable to the County.


CONTRACT: A 24-month contract ending TBD will apply to this tract. A sample of the timber sale contract, which may contain additional provisions, is available upon request. Timber sale contracts may not be assigned.

Legend

-  Gate
-  Berm
-  Rail road
-  Pond/Marsh
-  Trails
-  Stream

 Cut all aspen, ash & orange marked trees. Can reach across red paint lines to harvest ash trees. No operating equipment across red paint lines. Leave all dead trees standing. 6 Acres

 Overstory Removal: Cut all trees >1" except cedar, hemlock, & green marked trees. Sever all oak sapplings damaged during harvest operations. Can reach across red paint lines to harvest ash. No crossing red paint lines with equipment. Leave all dead trees standing. 24 acres.


 Oconto County Forest Lands

Sale #: _____

Tract 01-24 Forest Lake Sale Overview Map



No harvesting April 15th-July 15th due to oak wilt. 30 Acres



SESE Sec 9, SWSW Sec 10, SESW Sec 15 27N R20E Town of Abrams
Scale 1:15840



This map is neither a legally recorded map nor a survey and is not intended to be used as such. This map contains a compilation of records, information, and data to be used for reference purposes only. Oconto County is not responsible for any inaccuracies herein contained.

PROPERTY: Oconto County Forest
TRACT: 08-24
LOCATION: PT OF SWNE, SENW, & NENW, Section 29, T30N, R18E
TOWN NAME: Bagley
SALE AREA: 25 Acres

Bid Opening: May 6th, 2024 at 1:00 pm at Oconto County Courthouse. Any and all bids may be rejected

Species	Product	Volume	Weight Conversion
Aspen	Pulp/bolts	700 Tons	2.25 tons/cord
Mixed Hardwoods ¹	Pulp/bolts	240 Tons	2.4 tons/cord
Oak	Pulp/bolts	95 Tons	2.75 tons/cord
Balsam Fir	Pulp/bolts	130 Tons	2.125 tons/cord
White Pine	Mixed Products	30 Tons	2.1 tons/cord
Red Pine	Mixed Products	35 Tons	2.25 tons/cord
Oak	Sawtimber	1 MBF	
Red Maple ²	Sawtimber	1.5 MBF	

¹Mixed Hardwoods consists of ~80% Red Maple, 16% Ash, & 4% other.

²Any other species (Ash, Birch) processed as a log will be scaled as a Red Maple

SALE BOUNDARY: Red paint lines indicate sale boundary. Yellow paint lines indicate Riparian Management Zones (RMZ). All paint lines are facing sale area- cutting specifications shall be followed within the paint boundaries. If a discrepancy exists between this written description and the map, then this written description will prevail.

CUTTING SPECS:

Aspen Clearcut (25 acres): Cut and/or harvest all trees >1" EXCEPT White Oak, Hemlock, Cedar, Hawthorn, White Pine <5" (unless wind-damaged), & green-marked trees. Cut all wind-damaged trees- defined as uprooted, laying on ground, bent/leaning >30 degrees, snapped or broken trunk/bole, and/or missing >50% of the crown. DO NOT cut sale boundary trees marked in red or RMZ boundary trees marked in yellow UNLESS they are an Aspen.

Special Sale Considerations- ALL units:

- Oconto County Forestry Dept. will be doing road improvement work on CFR 205 summer 2024
- CFR 205 is a snowmobile & UTV/ATV trail
- All paint-line trees are NOT designated for harvest- do not cut unless given permission by Oconto County staff
- Stream Crossing: Oconto County staff will require, at a minimum, timber mats be used to cross the stream with logging equipment only (i.e. no logging trucks), and that the mats extend a minimum of 35-ft (RMZ width) on both sides of the stream crossing to prevent rutting and/or compaction of soils. Contractor may modify these requirements ONLY if they provide the same or greater water & ground protection.
- RMZ's: Northern Unit: The sale boundary line, indicated with a red paint line, is the high water mark (OHWM). No equipment or harvesting is allowed past the red line. The yellow-paint line indicates the 75-ft. RMZ. Equipment will be allowed during frozen or very dry ground conditions only. No landings or roads will be allowed in the RMZ. Southern Unit: A 35-ft RMZ, indicated by a yellow paint line, is on both sides of the stream. No equipment, landings, or roads will be allowed within the RMZ. Aspen within the RMZ may be harvested IF not dropped in stream & limits damage to residuals within the RMZ.
- There are 2 non-forested wetlands within the sale area. These areas are identified on the sale map & surrounded by a red paint line within the sale area. No equipment will be allowed to operate past the red line within the non-forested wetlands. No slash, tops, logging debris, etc will be allowed to remain in the wetlands.
- The sale area east of the stream crossing has areas with wetter soils. Permission from OC forestry staff will be required to operate in this area under non-frozen ground conditions.
- Equipment must arrive on-site clean & free of debris, dirt, etc.
- Dry or frozen ground conditions required.
- Decking areas & haul roads must be pre-approved by Oconto County staff.

UTILIZATION STANDARDS: Cord wood (aka pulp) must be utilized to a 4 inch top diameter for hardwoods and 4-inch for softwood. **Logs will be defined as 8 feet or longer to an 11-inch small end diameter for hardwoods and 9-inch small end diameter for soft woods.** Slash height shall not exceed 33".

SCALING METHOD: Review contract regarding specific scaling procedures & specifications. Ensure all employees, sub-contractors, etc. understand scaling & hauling procedures & the species/products specific to the sale. A list of anticipated wood vendors is required prior to hauling. Cord wood delivered to approved mills with certified scales must use truck/mill ticket system. Cord wood not going to mill with certified scale will be scaled on the landing. Sawtimber delivered to approved mills (3rd party log scale) may be hauled using the ticket system. Sawtimber not going to approved mills (not 3rd party scaled) must be scaled on the landing. Oconto County reserves the right to scale any & all wood products. Piles must be sorted according to species listed per contract. All stumpage payments are due upon receipt of the billing invoice. If payment is not received by close of business, 30 days from the date of the invoice, a penalty of 1.5% of the value on the invoice will be added each month. In addition, purchaser will be required to pay for forest products prior to removal until all invoices are paid in full.

CERTIFICATION: Logging Contractor (not necessarily the purchaser if subcontracted) must document compliance with Wisconsin SFI training standard. Successful bidders when signing a contract shall provide the county with workmen's compensation as required by Wisconsin Law and liability insurance with minimum combined single limit of \$1,000,000. Sub-contractors are also required to provide workmen's compensation and liability insurance as required by Wisconsin Law.

BOND REQUIREMENTS: A 10% Bid Bond must accompany each bid. Bond can be in the form of personal check, certified check, bank draft, or money order. Oconto County may retain the bid bond if the successful bidder fails to sign the contract. The Purchaser within 6 weeks of bid opening and before work is commenced must submit a 20% Performance Bond acceptable to the County.

CONTRACT: A 24 month contract ending TBD will apply to this tract. A sample of the timber sale contract, which may contain additional provisions, is available upon request. Timber sale contracts may not be assigned.

SEE MAP on PAGE 3

Legend


-  Section corners
-  streams
-  County Road
-  Trails
-  County forest road
-  Oconto County Forest
-  gate
-  Aspen Clearcut
-  Leave areas
-  RMZ paint line

Sale #
Tract 08-24
Hawthorn Hope Sale



Aspen Clearcut): Cut and/or harvest all trees >1" EXCEPT White Oak, Hemlock, Cedar, Hawthorn, White Pine <5" (unless wind-damaged), & green-marked trees. Cut all wind-damaged trees- defined as uprooted, laying on ground, bent/leaning >30 degrees, snapped or broken trunk/bole, and/or missing >50% of the crown. DO NOT cut sale boundary trees marked in red or RMZ boundary trees marked in yellow UNLESS they are an Aspen

25 acres



PT OF SWNE, SENW, NENW, Section 29,
T30N, R18E, Town of Bagley, Oconto County,
WI

Firgens

Scale 1:10,560

6"=1 mile



This map is neither a legally recorded map nor a survey map and is not intended to be used as such. This map contains a compilation of records, information, and data to be used for reference purposes only. Oconto County is not responsible for any inaccuracies herein contained.

PROPERTY: Oconto County Forest
TRACT: 09-24
LOCATION: PT OF NENE, SENE, Section 2, T30N, R17E
TOWN NAME: Breed
SALE AREA: 25 Acres

Bid Opening: May 6th, 2024 at 1:00 pm at Oconto County Courthouse. Any and all bids may be rejected

Species	Product	Volume	Weight Conversion
White Pine	Mixed Products	625 Tons	2.1 tons/cord
Red Pine	Mixed Products	230 Tons	2.25 tons/cord
Aspen	Pulp/bolts	180 Tons	2.25 tons/cord
Mixed Hardwoods ¹	All	50 Tons	2.4 tons/cord
Oak	All	35 Tons	2.75 tons/cord

¹Mixed Hardwoods is 75% Red Maple with remaining comprised of Birch, Beech

SALE BOUNDARY: Red paint line indicates north boundary, Blue paint lines indicates west sale boundary (bordering private lands), Robenhorst Lane represents south sale boundary, Robenhorst Road represents east sale boundary. Within sale area, purple paint line indicate existing gaps & are "leave" areas. If a discrepancy exists between this written description and the map, then this written description will prevail.

CUTTING SPECS: White Pine Shelterwood- Cut all trees >1" EXCEPT White Oak, White Pine <5", & green-marked trees. The preferred method to harvest/cut unmerchantable timber is to pull out of ground. Do not operate equipment, drop trees, or otherwise disturb the gaps indicated by the purple paint lines. Harvesting trees beyond purple paint lines is allowed ONLY if doing so will not harm existing White Pine regeneration within the gap. Heterobasidion Root Disease (HRD) treatment is required from April 1st-November 30th on cut pine & spruce. Cut pine cannot be stored on site more than 14 days from May 1st-August 31st.

Special Sale Considerations-

- Any operator applying CelluTreat, or any other chemical, is required to have a DATCP-endorsed Commercial Pesticide Applicator License
- Any & all paint-line trees are NOT designated for harvest- do not cut unless given permission by Oconto County staff
- Leaf-off conditions required for harvesting operations to occur. Allowable time frame will be set starting October 31 and ending April 1st unless permission is granted by Oconto County staff to operate outside of that time frame.
- Do not fell trees onto and/or leave any slash or logging debris on town road or town ROW OR across any red, blue, or purple paint line
- Equipment must arrive on-site clean & free of debris, dirt, etc.
- Dry or frozen ground conditions required.
- Decking areas, spur/haul roads, and any earth-work (dozer, etc.) must be pre-approved by Oconto County staff.

UTILIZATION STANDARDS: Cord wood (aka pulp) must be utilized to a 4 inch top diameter for hardwoods and 4-inch for softwood. Slash height shall not exceed 33".

SCALING METHOD: Review contract regarding specific scaling procedures & specifications. Ensure all employees, sub-contractors, etc. understand scaling & hauling procedures & the species/products specific to the sale. A list of anticipated wood vendors is required prior to hauling. Cord wood delivered to approved mills with certified scales must use truck/mill ticket system. Cord wood not going to mill with certified scale will be scaled on the landing. Sawtimber delivered to approved mills (3rd party log scale) may be hauled using the ticket system. Sawtimber not going to approved mills (not 3rd party scaled) must be scaled on the landing. Oconto County reserves the right to scale any & all wood products. Piles must be sorted according to species listed per contract. All stumpage payments are due upon receipt of the billing invoice. If payment is not received by close of business, 30 days from the date of the invoice, a penalty of 1.5% of the value on the invoice will be added each month. In addition, purchaser will be required to pay for forest products prior to removal until all invoices are paid in full.

CERTIFICATION: Logging Contractor (not necessarily the purchaser if subcontracted) must document compliance with Wisconsin SFI training standard. Successful bidders when signing a contract shall provide the county with workmen's compensation as required by Wisconsin Law and liability insurance with minimum combined single limit of \$1,000,000. Sub-contractors are also required to provide workmen's compensation and liability insurance as required by Wisconsin Law.

BOND REQUIREMENTS: A 10% Bid Bond must accompany each bid. Bond can be in the form of personal check, certified check, bank draft, or money order. Oconto County may retain the bid bond if the successful bidder fails to sign the contract. The Purchaser within 6 weeks of bid opening and before work is commenced must submit a 20% Performance Bond acceptable to the County.

CONTRACT: A 24-month contract ending TBD will apply to this tract. A sample of the timber sale contract, which may contain additional provisions, is available upon request. Timber sale contracts may not be assigned.



Sale # _____
Tract 09-24
Red-Head White Pine Sale


Legend

- gate
- Section corners
- Roads
- Trails
- White Pine Shelterwood
- Lake
- Oconto County Forest
- Gaps

-White Pine Shelterwood- Cut all trees >1" EXCEPT White Oak, White Pine <5", & green-marked trees. Preferred method to harvest/cut unmerchantable timber is to pull out of ground. Do not operate equipment, drop trees, or otherwise disturb the gaps indicated by the purple paint lines. Harvesting trees beyond purple paint lines is allowed ONLY if doing so will not harm existing White Pine regeneration within the gap.

-Heterobasidion Root Disease (HRD) treatment is required from April 1st-November 30th on cut pine & spruce. Cut pine cannot be stored on site more than 14 days from May 1st-August 31st.

25 acres



SENE, NENE, Section 2, T30N, R17E
Town of Breed, Oconto County, WI
Scale 1:7920 8"=1 mile

Firgens



This map is neither a legally recorded map nor a survey map and is not intended to be used as such. This map contains a compilation of records, information, and data to be used for reference purposes only. Oconto County is not responsible for any inaccuracies herein contained

Township: **Breed**
T30N, R17E, Sec 2

Approximate cutting area: **25** acres

Bond Info: **PreBidValue 23,927.00**

Choose method by which performance bond will be posted or secured.
 Please check one: Cash or Check Irrevocable Letter of Credit

Product Species	Estimated Unit Volume	Bid Per Unit	Total
18T-PW Comingled White Pine	625.00 Tons	_____	_____
18T-PR Comingled Red Pine	230.00 Tons	_____	_____
20T-A Aspen Pulp	180.00 Tons	_____	_____
20T-MX Mixed Hdwd Pulp	50.00 Tons	_____	_____
20T-OO Oak Pulp	35.00 Tons	_____	_____
			Total Bid

Acceptable bids must meet or exceed the total combined advertised value. If an error on a bid form is discovered, the price per unit, as indicated on the form by the bidder multiplied by the estimate of the county will be used to determine total sale bid value. Tie bidders will be offered an opportunity to withdraw. If none withdraw, tie bidders will be required to submit another sealed bid within 2 days of bid opening.

NOTE: This bid, when properly filled out, should be placed in a plain envelope and sealed. Mark the envelope 'Timber Bid - Tract #', indicate the Tract No. and enclose the 10% bid bond. Place this sealed envelope in a mailing envelope and mail to the Oconto County Forest & Parks Department, 301 Washington St., Oconto, WI 54153. Bids may be hand delivered in a sealed envelope to the office. Check bid notice for deadline date and time. For more information, please call 920-834-6995. See Timber Bid Conditions on the Timber Sale Prospectus.

Name _____

Address _____

City, State, Zip _____

Phone # _____

Bidder Signature _____

e-mail _____

Date _____

Township: **Bagley**
T30N, R18E, Sec 29

Approximate cutting area: **25** acres

Bond Info: **PreBidValue 10,999.40**

Choose method by which performance bond will be posted or secured.
 Please check one: Cash or Check Irrevocable Letter of Credit

Product Species	Estimated Unit Volume	Bid Per Unit	Total
20T-A Aspen Pulp	700.00 Tons	_____	_____
20T-MX Mixed Hdwd Pulp	240.00 Tons	_____	_____
20T-OO Oak Pulp	95.00 Tons	_____	_____
20T-F Fir Pulp	130.00 Tons	_____	_____
18T-PW Comingled White Pine	30.00 Tons	_____	_____
18T-PR Comingled Red Pine	35.00 Tons	_____	_____
10-OO Oak Sawlogs	1.00 MBF	_____	_____
10-MR Red Maple Sawlogs	1.50 MBF	_____	_____
			Total Bid

Acceptable bids must meet or exceed the total combined advertised value. If an error on a bid form is discovered, the price per unit, as indicated on the form by the bidder multiplied by the estimate of the county will be used to determine total sale bid value. Tie bidders will be offered an opportunity to withdraw. If none withdraw, tie bidders will be required to submit another sealed bid within 2 days of bid opening.

NOTE: This bid, when properly filled out, should be placed in a plain envelope and sealed. Mark the envelope 'Timber Bid - Tract #', indicate the Tract No. and enclose the 10% bid bond. Place this sealed envelope in a mailing envelope and mail to the Oconto County Forest & Parks Department, 301 Washington St., Oconto, WI 54153. Bids may be hand delivered in a sealed envelope to the office. Check bid notice for deadline date and time. For more information, please call 920-834-6995. See Timber Bid Conditions on the Timber Sale Prospectus.

Name _____

Address _____

City, State, Zip _____

Phone # _____

Bidder Signature _____

e-mail _____

Date _____

Township: **Abrams**

Approximate cutting area: **30** acres

T27N, R20E, Sec 9, 10 & 15

Bond Info:

PreBidValue

26,047.60

Choose method by which performance bond will be posted or secured.

Please check one: Cash or Check Irrevocable Letter of Credit

Product Species	Estimated Unit Volume	Bid Per Unit	Total
20T-MX Mixed Hdwd Pulp	1,600.00 Tons	_____	_____
20T-BA Bass Wood Pulp	65.00 Tons	_____	_____
20T-OO Oak Pulp	35.00 Tons	_____	_____
20T-A Aspen Pulp	25.00 Tons	_____	_____
20T-F Fir Pulp	25.00 Tons	_____	_____
10-MR Red Maple Sawlogs	60.00 MBF	_____	_____
10-MX Mixed Hardwood Sawlogs	15.00 MBF	_____	_____
10-OR Red Oak Sawlogs	2.00 MBF	_____	_____
			Total Bid

Acceptable bids must meet or exceed the total combined advertised value. If an error on a bid form is discovered, the price per unit, as indicated on the form by the bidder multiplied by the estimate of the county will be used to determine total sale bid value. Tie bidders will be offered an opportunity to withdraw. If none withdraw, tie bidders will be required to submit another sealed bid within 2 days of bid opening.

NOTE: This bid, when properly filled out, should be placed in a plain envelope and sealed. Mark the envelope 'Timber Bid - Tract #', indicate the Tract No. and enclose the 10% bid bond. Place this sealed envelope in a mailing envelope and mail to the Oconto County Forest & Parks Department, 301 Washington St., Oconto, WI 54153. Bids may be hand delivered in a sealed envelope to the office. Check bid notice for deadline date and time. For more information, please call 920-834-6995. See Timber Bid Conditions on the Timber Sale Prospectus.

Name _____

Address _____

City, State, Zip _____

Phone # _____

Bidder Signature _____

e-mail _____

Date _____

Advertised species, products and value for sale tract#: 13-21

Township: **Little River**
T29N, R22E, Sec 14 & 15

Approximate cutting area: **99** acres

Bond Info: **PreBidValue** **29,249.00**

Choose method by which performance bond will be posted or secured.
 Please check one: Cash or Check Irrevocable Letter of Credit

Product Species	Estimated Unit Volume	Bid Per Unit	Total
20T-MX Mixed Hdwd Pulp	2,500.00 Tons	_____	_____
20T-A Aspen Pulp	1,400.00 Tons	_____	_____
20T-OO Oak Pulp	130.00 Tons	_____	_____
10-MR Red Maple Sawlogs	60.00 MBF	_____	_____
10-AS Ash Sawlogs	55.00 MBF	_____	_____
10-OO Oak Sawlogs	15.00 MBF	_____	_____
10-MX Mixed Hardwood Sawlogs	4.00 MBF	_____	_____
			Total Bid

Acceptable bids must meet or exceed the total combined advertised value. If an error on a bid form is discovered, the price per unit, as indicated on the form by the bidder multiplied by the estimate of the county will be used to determine total sale bid value. Tie bidders will be offered an opportunity to withdraw. If none withdraw, tie bidders will be required to submit another sealed bid within 2 days of bid opening.

NOTE: This bid, when properly filled out, should be placed in a plain envelope and sealed. Mark the envelope 'Timber Bid - Tract #', indicate the Tract No. and enclose the 10% bid bond. Place this sealed envelope in a mailing envelope and mail to the Oconto County Forest & Parks Department, 301 Washington St., Oconto, WI 54153. Bids may be hand delivered in a sealed envelope to the office. Check bid notice for deadline date and time. For more information, please call 920-834-6995. See Timber Bid Conditions on the Timber Sale Prospectus.

Name _____

Address _____

City, State, Zip _____

Phone # _____

Bidder Signature _____

e-mail _____

Date _____