## DNR TRACT NO. 948-10 Powell Marsh

## Vilas/Iron County

## Town 42 North, Range 4 East

Section 25 - SESE

Section 36 - Gov Lot 1,4 & 5

### Town 42 North, Range 5 East

Section 20 - Gov Lot 6

Section 21 - Gov Lot 5, NESE

Section 30 — SWSW, SESW, SWSE

Section 31 - Gov Lot 1, NENW

Section 33 - SENE

10% of the total sale bid value will be required as bid bond.

15% of the total sale bid value will be required for performance bond.

The cutting area is approximately 93 acres.

The contract period is 3 years.

All trees that will yield one or more 100-inch sticks to the minimum top diameter 4" will be cut and utilized.

# ESTIMATED VOLUME (CORDS) MINIMUM TOP DIAMETER

		Whole Tree	Advertised Price Per Unit	
SPECIES	<u>4"</u>			
Mixed Hardwood <sup>1</sup>	950		\$	29.60
Aspen	800		.\$	28.80
Balsam Fir <sup>2</sup>	90		\$	15.20

Total Minimum Bid Value \$ 52,528.00

#### Special Conditions

- 1. Cutting must be concurrent for all species to be harvested.(9)
- Slash within 50' of recreational trails, town, and county roads must be lopped and/or scattered to lie
  within two feet of the ground and pulled back at least ten feet behind the tree line concurrently with
  cutting. (16)
- All trails must be repaired to pre-harvest conditions following the harvest. The woods roads which
  will be opened up and used during the harvest, will be dressed and bermed following harvest
  completion by the contractor.(18)
- Landing sites and new haul roads need to be approved by the administering forester during the pre sale meeting with the logging contractor and as need arises. (18)
- Tops and slash which fall in lowland swamp areas must be pulled back into harvest area prior to limbing and bucking. (16)
- 6. No hauling or skidding down ski trail, only crossing at designated spots.(18)
- Short wood skidding required in hardwood and over story removal areas.
- 8. Whole tree chipping/biomass harvesting not permitted.(9)
- 9. Frozen ground harvesting required in all harvesting areas.(9)
- Snowmobile trail crossing location will need to be kept free of harvesting debris and have a snow base intact during harvesting operations. (18)
- 11. Woods roads can be cut open and improved prior to ground freeze up for ease of equipment operation.

Approximately 47% white birch, 38% red maple, 15% hard maple.

Approximately 76% balsam fir, 12% red pine, 12 % white pine.



